

NOTES! DPTI STANDARD = 25x25x3.15 GALV WELDMESH. PANELS TO BE FABRICATED FROM 40x40x3 EQUAL ANGLE, 25x25x3.15 OR 50x50x4.0 GALV WELDMESH. TO BE CONFIRMED PRIOR TO FABRICATION. LINSH OUTSIDE WELDS TO SMOOTH FINISH. HOT DIP GALV ALL PANELS, & REMOVE ANY EXCESS SHARP ZINC COATING CAUSED BY GALV PROCESS.

PANELS TO INTERLOCK ON ASSEMBLY, BOLT SIDES & FRONT/BACK PANELS TOGETHER. PADLOCK & HINGES TO SECURE TOP PANEL IN PLACE. FIX IN PLACE WITH M10 CHEM ANCHOR, 80mm MIN EMBEDMENT.

WHERE POSSIBLE, PANELS TO BE SUPPLIED 'FLAT PACKED' TO SITE. SPECIAL ORDERS MAY REQUIRE WORKSHOP ASSEMBLY, AND SOME SITE ASSEMBLY. IF SITE WELDING IS REQUIRED, ALL WELDS TO BE TOUCHED UP WITH ZINC RICH PRIMER, AND NEAT APPLICATION OF SILVERFROST

ENGINEERING

23 HEATH STREET LONSDALE SOUTH AUSTRALIA 5160

AUSTRALIA. Ph 08 8187 2888. Fax 08 8326 8654 EMAIL. sales@saxonengineering.com.au admin@saxonengineering.com.au

THIS DOCUMENT IS COPYRIGHT AND REMAINS THE PROPERTY OF SAXON ENGINEERING, AND MUST NOT BE USED, REPRODUCED OR COPIED, WHOLLY OR IN PART, WITHOUT THE WRITTEN PERMISSION OF SAXON ENGINEERING.

PUMP CAGE TITLE: 1600x500x500 TYPICAL DETAILS

SITE:

CLIENT:

19/07/17

JLILINI.				
SCALE (S)	AS SHOWN		JOB No:	
DRAWN	CHECKED	SIZE	DRAWING	NUMBER
TAG				

REV.

PC1-01-01